



IN THE CLAIMS

Please amend the status of the claims to that indicated as follows:

Claims 1-19 (canceled)

20. (previously presented) A playhouse made from pre-fabricated parts, comprising:

supporting posts having limit stops or locking elements and being formed as vertical plate-like bodies with horizontal slits; and,

a roof affixed to said supporting posts, said roof being a self-supporting slab resting in a horizontal direction directly upon, and positioned in, said horizontal slits of said supporting posts with said supporting posts vertically extending beyond said self-supporting slab, and with said self-supporting slab and said supporting posts being stably connected without permanent fixation means, thereby permitting said playhouse to be readily dismountable and transportable.

21. (previously presented) The playhouse made from pre-fabricated parts according to Claim 20, wherein said self-supporting slab comprises a cover plate which, in a parallel direction, rests upon a level framework to which it is connected.

22. (previously presented) The playhouse made from pre-

fabricated parts according to Claim 20, wherein said self-supporting slab is shaped as a hexagon.

23. (previously presented) The playhouse made from prefabricated parts according to Claim 20, wherein said self-supporting slab is shaped as a half-hexagon.

24. (previously presented) The playhouse made from prefabricated parts according to Claim 20, wherein said supporting posts have a horizontal cross-section which is bent or curved.

25. (previously presented) The playhouse made from prefabricated parts according to Claim 20, wherein said supporting posts are provided with recesses.

26. (previously presented) The playhouse made from prefabricated parts according to Claim 20, wherein said supporting posts have a length exceeding a distance as measured from said roof to a floor level of said playhouse, and having a recess into which said self-supporting slab is capable of being inserted edgewise.

27. (previously presented) The playhouse made from prefabricated parts according to Claim 20, wherein said vertical plate-like bodies are comprised of straw with a binding agent.

28. (previously presented) The playhouse made from pre-

fabricated parts according to Claim 20, wherein said self-supporting slab includes a fastening device on its base or an edge thereof.

29. (previously presented) The playhouse made from pre-fabricated parts according to Claim 28, wherein said fastening device is a guide rail.

30. (previously presented) The playhouse made from pre-fabricated parts according to Claim 20, wherein said self-supporting slab has a side rail on its top side.

31. (previously presented) The playhouse made from pre-fabricated parts according to Claim 20, wherein parts of said playhouse are connected to one another via plug connections.

32. (previously presented) The playhouse made from pre-fabricated parts according to Claim 20, wherein said permanent fixation means includes screw connections.

Claims 33-34 (canceled)

35. (previously presented) The playhouse made from pre-fabricated parts according to Claim 20, wherein each said locking elements of said supporting posts comprises a lockable extension provided edgewise with a hook, said hook being pushable through an aperture in a support for each said locking elements, a cross-section of said aperture being

diminished by said locking element so that said hook cannot be pulled outwardly from said aperture.